

# **TOC-20 SERIES**

# **Refrigerant Gas Monitor**



# Installation and Operation Manual Version 4





Triton House

Stockport

SK2 6SH

England

Crosby Street

Tel: +44 (0)161 483 1415 Fax: +44 (0) 161 484 2345 Email: sales@internationalgasdetectors.com Website: www.internationalgasdetectors.com

FS646773

Document Ref: T20-V4



Blank Page









#### INDEX

#### Page

- 3 CE Declaration
- 4 Gen Specifications
- 5 Main electrical Connection Points
- 7 Controller Overview
- 8 User Actions Day to Day Operation
- 9 Display Access and Menu Operation
- 10 Menu Overview
- 11 Monitoring CFC/HCFC Plants
- 12 Warm Up Sequence
- 12 Supplied Set up
- 13 Relay Connections
- 13 Analogue Output (mA Option)
- 14 Analogue Output (Volts Option)
- 15 Putting into Service Summary
- 16 Alarm Level Setup
- 17 Alarm Type Setup
- 18 Alarm Relay
- 18 Alarm Summary
- 19 4-20mA Ouput Calibration & Test
- 20 4-20mA Output Zero & Calibration Functions

#### Who should read this manual.

This manual is intended for use by trained installers of gas detection systems who are technically competent and have all necessary tools to undertake installation and maintenance on this type of equipment.

Failure to install and maintain the equipment properly can render the detector ineffective.

You should not undertake any of the procedures in this manual if you do not have access to the correct equipment, have not undertaken training on this or similar equipment or are not technically qualified to install this equipment.

Calibration gases and test equipment is available from Sensors.





Triton House

Stockport

SK2 6SH

England

Crosby Street





# **EC Declaration of Conformity**

Issuers name and address

Declares that the product listed as:

Oliver IGD Limited of Triton House Crosby St, Stockport, United Kingdom

**TOC-20** 

4-20mA or Addressable Output Gas Detector with display

Are in conformity with the provisions of the following European Directive(s) when installed, operated, serviced and maintained in accordance with the installation and operating instructions contained in the product documentation.

2004/108/EC 2006/95/EC	EMC Directive Low Voltage Equipment Directive (note not applicable to 24V DC Powe	red Versions)
And that the standa	rds and/or technical specifications referenced below have been applied or	considered.
EN 61779-1:2000	Electrical apparatus for the detection and measurement of flami requirements and test methods.	nable gases, general
EN 50271:2010	Electrical apparatus for the detection and measurement of combound of combound of combound of the state of th	oustible gases, toxic gases or nd or digital technologies.
EN 61000-6-2: 200 EN 61000-6-4: 200 EN 61000-3-2/A2:2 EN 61000-3-3: 200	<ul> <li>EMC Generic standards. Immunity for industrial environments</li> <li>EMC Generic standards. Emission standard for industrial environments</li> <li>EMC Limits. Limits for harmonic current emissions (equipment i</li> <li>EMC Limits. Limitation of voltage changes, voltage fluctuations</li> <li>supply systems, for equipment with rated current ≤ 16 A per pha</li> </ul>	nments nput current ≤ 16 A per phase) and flicker in public low-voltage ase
Technical File Refe	rence T20-TE9	

Product Markings (E TOC-20	S/-serial number		
Oliver IGD Limited Operate and	Oliver IGD Limited operate an independently	Testing Agency:	
Independently assessed ATEX/IECEX QAN.	assessed ISO9001:2008 Quality Management System.	TUV - SUD	TIM
Quality Assurance Certificate Number ExVeritas 16PQAN0014	·	Octagon House Concorde Way	SUD
	Quality Management Certificate Number	PO 15 5RL	
Quality Assurance Notification Number:	FS 646773	Fareham	
2585			Achr Sicherheit.
ExVeritas,			MGIN WEIL
Units 16-18,	BSI Assurance UK LTD,		
Abenbury Way,	Chiswick High Road,		
Wrexham Industrial Estate,	London		
Wrexham, UK, LL13 9UZ	W4 4AL		
	UK		
TUV Certificates and reports can be checked or	n-line at <a href="https://www.tuev-sued.de/industry_and_consume">https://www.tuev-sued.de/industry_and_consume</a>	r_products/certificates	
Issued on: June2016 At C	liver IGD Limited, Stockport, SK2 6SH , United	d Kingdom	
Signature:	Declaration of Conformity in accordance	with EN ISO/IEC 170	50-1:2010
Name	Andrew J Collier M.I.O.D		

Position:

Managing Director

Date: June 2016

Declaration Ref: TOC-20DEC-3





Triton House

Stockport

SK2 6SH

England

Crosby Street





#### **Standard Specifications**

Power	18-28V DC (230V AC Adaptor Supplied)
Construction	ABS
Outputs	1 off 4-20mA Linear Output for CFC/HCFC Modbus RTU Interface 2 off SPCO Relays Rated 4A Non Inductive 85dB Alarm Sounder
Operating Environment	
Temperature Humidity Sealing	-5 to 55 Deg C 5-95% RH Non-Condensing IP54 (Excluding Sensor)

Measuring Ranges CFC/HCFC 0-1000ppm, Resolution 10ppm, Accuracy +/- 5% of Range

Initial Stabilisation	Typically up to 48 Hours on first installation Note for installers: Do not make adjustments to zero or calibration settings until the unit has fully stabilised.
Package Size	180mm X 100mm X 75mm (See Dimension Drawing)
Weight	375g

# **Physical Details**





 OLIVER
 Coling

 Triton House
 Crosby Street

 Crosby Street
 E

 Stockport
 E

 Stockport
 W

SK2 6SH

England





# NOTE

TOC-20 can be supplied with a bulkhead mounting PSU allowing permanent connection to a 230V AC mains power source. Mains power should be fed via a fused spur.

When working with stranded cable ensure ferrules (bootlaces) are fitted to prevent stray cable strands. The following information shows the main electrical connection points labelled as points and interfaces. These points are referred to in the manual supplied. When installing ensure you have the full manual available. This page is also supplied inside the TOC-20 enclosure as a quick reference for site engineers. If you do not have the full manual a copy is available on our website at www.internationalgasdetectors.com/downloads/

#### INTERFACES







Triton House

**Crosby Street** 

Stockport

SK2 6SH

England





# **Power Options Figure 2**



#### Notes





SK2 6SH

England







Typical display during warm up



On initial power up the backlight will perform the following cycle:

Backlight cycles: green-yellow-red

The display then shows:

Software Version Software checksum and date Connected sensor info

Finally a countdown starts to enable connected sensors to stabilise prior to normal operation.

From initial power up the TOC-20 will take 1 hour to stabilise. Additionally for a new installation it can take up to 48 hours for detectors to fully stabilise to new conditions.





Triton House

Stockport

SK2 6SH

England

Crosby Street





# User Actions....Day to Day Operation

Once fully installed the TOC-20 controller will continuously monitor the CFC level continuously comparing current values with any set alarm thresholds. The display will cycle to display each reading in turn. Normally the backlight will be green to indicate correct operation below set thresholds

To access the display click the button

Note that each channel will be displayed in turn as indicated by pressing the button. The background colour changes to blue to indicate manual channel selection. After 60s if the button is not pressed the display reverts to a green background and the display will revert to show each reading in turn.

# In Alarm Condition

The back light will flash red and the display will indicate which alarm level and which channel is in alarm. The sounder will also activate. Pressing the button will silence the sounder. If the gas is still breaching the alarm threshold it will not be possible to reset the alarm

#### In Fault Condition

In FAULT mode the Yellow fault led will be on. The bottom line of the display will indicate as follows:

FLT COMcommunication<br/>error to sensorsFLT SENSensor ErrorFLT OVRSensor Over RangeFLT UNDSensor Under Range





In the event of alarm or fault, CALL FOR SERVICE. The owner operator is not usually a gas engineer or competent person as defined by Health and Safety guidelines. If there is any doubt call your service company and get it checked.





Triton House

Stockport

SK2 6SH

England

Crosby Street





#### To access the display press the button for 1-2 seconds







Triton House Crosby Street Stockport SK2 6SH England











Triton House

Stockport

SK2 6SH

England

Crosby Street

Tel: +44 (0)161 483 1415 Fax: +44 (0) 161 484 2345 Email: sales@internationalgasdetectors.com Website: www.internationalgasdetectors.com



operation

FS646773



### Monitoring CFC/HCFC Plant Using T20-HFC or CFC Models

Here the TOC-20 is being used to monitor for possible leaks from fixed refrigeration or air conditioning plant. Good detector placement is key to ensuring correct operation. Most CFC's and HCFC's are heavier than air so it would be normal practice to place detectors below valve stations, manifolds and coils. Note that detectors cannot be placed in cold stores and should be away from areas of air movement such as ventilation fans. Avoid moisture and condensation onto units, enclosures are IP rated but the sensor is not, condensation and moisture ingress to the sensor can cause damage. IGD are available to advise on specific installations provided details are available. Inclusion for the detection at an early design stage is always adviseable.





Triton House

Crosby Street

Stockport

SK2 6SH

England

Tel: +44 (0)161 483 1415 Fax: +44 (0) 161 484 2345 Email: sales@internationalgasdetectors.com Website: www.internationalgasdetectors.com



FS646773



With the TOC-20 correctly located and powered the system will perform a self check then proceed through its stabilisation period. This is 1 hour, during this period the sensors are stabilising to their environment, during this period the alarm relay outputs are inactive and the analogue outputs will indicate zero. At the end of the stabilisation period the system will go into normal operation.

## **Normal Operation**

In normal operation mode the TOC-20 displays each channel and its reading in turn. In normal mode the back light will be green. Pressing the button will change the backlight to blue, indicating manual mode. each button press then indicates the next channel reading. After 60 seconds without a button press the system reverts to normal operation.



# Supplied Set Up

The T20-HFC-1000 will be supplied with the following default set up.

	Channel 3 CFC 0-1000ppm
Alarm 1 Level	500 ppm
Alarm 1 Relay	Relay 1
Sounder	On
Alarm 2 Level	800ppm
Alarm 2 Relay	Relay 2
Sounder	On
Analogue Output	3





Triton House

Crosby Street

Stockport

SK2 6SH

England





### **Relay Connection**

As standard the TOC-20 system is equipped with two relay outputs. The function of these two relay outputs can be user configured and is discussed in a later section. The relays are rated to operate 4A non inductive loads. Typical wiring arrangements are indicated below and show typical methods to protect the relays during installation.



External E-Stop

# Analogue Outputs (mA)

As standard the TOC-20 is equipped with three analogue outputs. By default these are configured as 4-20mA current outputs. By request these can be set to 0-10V DC outputs during production. This is a factory only setting. The following diagrams indicate the connections



Triton House

Crosby Street

Stockport

SK2 6SH

England



Note this diagram shows the use of screened cabling when interfacing signal cables. Signal cables should be segregated from power and control cables for best results.









# Analogue Outputs (Voltage)

If requested at the time of ordering the TOC-20 can be supplied with its analogue outputs re-

configured as 0-10V DC. The following diagrams indicate the connections

0-10V Analogue Output Interfaces



Note this diagram shows the use of screened cabling when interfacing signal cables. Signal cables should be segregated from power and control cables for best results.

Testing Appleque Outputs	OUTPUT 1	OUTPUT 2	]	OUTPUT 3	
	4 OF 9	5 OF 9		6 OF 9	

The operating system has a simulation mode for the analogue output channels. This allows the commissioning engineer to force a signal output to prove correct interfacing at the host system.







Triton House

Stockport

SK2 6SH

England

**Crosby Street** 





## Putting into Service Test Schedule

In conclusion by following the steps discussed your checklist for putting into service should be:

- 1 Ensure Location of the TOC-20 is optimum for the application. If the bulkhead PSU option is being used then ensure this is fed from a fused spur.
- Ensure terminations via glands provide a positive seal.
   Leave all interfaces unplugged and check installation cabling terminations
- 3 Check the required alarm setup has been entered. Amend the default alarm set up if required Power up the TOC-20. Allow the system to stabilise and that the normal green display is indicated at the end of the stabilisation period with no faults indicated.
- 4 If the relay outputs are being used check the cabling then plug in and test using the TST RLY function the relay action.
- 5 If the analogue outputs are being used check the cabling to connector 1, plug in and test using the OUTPUT 1, 2 or 3 functions.
- 6 After stabilisation is complete the display should indicate zero with no leaks present.
- 7 The normal response for the sensors is 90 seconds to 90% of final reading. This is the FAST response setting. In some applications, such as densely populated call centres this may be too fast. If a slower response is required to reduce peak readings then choose either the Medium or Slow settings in the engineer menu RESPONSE option.
- 8 The TOC-20 should now be operating correctly

In the event that the controller needs amendment to set up follow the instructions in the following sections.

Changing alarm levels

Assigning relay outputs

Zero and Calibration Function (analogue outputs)

Calibration of the sensors is not covered in this manual and should only be undertaken by a trained engineer with the appropriate equipment and software.

NOTE: Detectors will require a period of time to stabilise to the environment into which they are installed. It is quite normal for this to take up to 48 Hours.

Do not use Aerosol or other cleaning agents with the detector, these can upset readings.





Triton House

**Crosby Street** 

Stockport

SK2 6SH

England





# Alarm Level Set Up

ALARM 1	
3 OF 8	

ALARM 2 4 OF 8

As previously described enter password mode and enter password 100 to enter the user menu. Press the button until either menu 3 or 4 is displayed and hold the button until prompted to release. The set up sequence for the alarm level selected is as follows:



and hold the button until prompted to release.



Each button press increments the indicated alarm level. To access more options press and hold the button until prompted to release and the following menu choices are available at each button press. Again to select the desired option when displayed press and hold the button until prompted to release.

DEC TEST	—— Select to DECrease the alarm level
INC TEST	Select to INCrease the alarm level
 DONE TEST	Select if the correct alarm level is displayed and you want to store it onto the system.
 CANCEL TEST	Select to exit the sequence without making changes



OLNES

Triton House

Stockport

SK2 6SH

England

Crosby Street





Once the alarm level has been set you then need to set the Alarm TYPE and decide which relay activates once the set alarm level is breached. The following sequence continues from the previous page and describes the set up sequences



England

FS646773

18 of 20

Once the alarm TYPE has been set you then need to set the RELAY output, that is deciding which relay activates once the set alarm level is breached. The following sequence continues from the previous page and describes the set up sequence



To select an option press and hold the button until prompted to release.



Each button press increments the indicated relay to activate. Note that relays 1 and 2 are physically on the control panel. If you increment past 2 then the panel assumes the relay is addressable and jumps to start from 4201. In this case enter the address of the addressable relay to activate. To access more options press and hold the button until prompted to release and the following menu choices are available at each button press. Again to select the desired option when displayed press and hold the button until prompted to release.

 DEC TEST	—— Select to DECrease the relay number
 INC TEST	—— Select to INCrease the relay number
 DONE TEST	Select if the correct relay number is displayed and you want to store it onto the system.
 CANCEL TEST	Select to exit the sequence without making changes

Selecting SUMMARY from this group of menu options allows you to see what has already been set up



To select an option press and hold the button until prompted to release.



In this example a two channel system has two alarm level 1's set up. When you enter the option alarm level one settings for the channel are displayed. Click the button to return to the previous menu options. To view alarm level 2 settings go back and select ALARM2 option. Note you only view the summary one channel at a time.







Crosby Street

Stockport

SK2 6SH

England





# CALIBRATIONS

# 4-20mA Output Calibration and Test

The TOC-20 is equipped with three 4-20mA analogue outputs. By default these are configured so that output 1 relates to input channel 1, output 2 is input channel 2 and output 3 is input channel 3. The TOC-20 is shipped with these channels pre-calibrated. It should not normally be necessary to calibrate these channels. The system has functions to allow zero, calibration and test of these channels as follows:

The following sequence discusses calibration for channel 3. The sequence is the same for each channel. As indicated in the diagram connect a multimeter on its mA scale between 0V DC and the output to be tested, in this case signal 3 (on connector 1).



mA Analogue Output Interfaces



As previously described enter password mode and enter password 50 to enter the engineer menu. Press the button until either menu 3, 4 or 5 is displayed depending on the required output channel and hold the button until prompted to release. The following sequence shows output 1 being calibrated as an example .:







Triton House

Crosby Street

Stockport

SK2 6SH

England





#### 4-20mA Output Zero Function







Triton House

Stockport

SK2 6SH

England

Crosby Street

